# Safe shutdown and isolation

Before physical inspection, follow site-specific safety procedures and lockout/tagout requirements. Only authorized personnel may isolate equipment. Identify all energy sources, including electrical supply, stored mechanical energy, gravity, and driven equipment. Apply the approved isolation devices and personal locks, release or restrain stored energy using site procedure, and verify the safe state with approved methods before work. A stop command or open control switch is not proof of isolation. If isolation cannot be confirmed, do not proceed.

# Electrical hazards

Electrical enclosures and terminals present shock and arc-flash hazards. Work is limited to qualified personnel operating within their training, authorization, and site electrical safety program. Use the site's risk assessment, boundaries, protective equipment, and test instruments. Never open an energized enclosure for routine visual inspection. Report damaged cables, arcing, burning odor, or water ingress and keep others clear according to site procedure.

Original synthetic content · Not manufacturer guidance

# Restart and handback

Before returning equipment to service, account for people and tools, reinstall all guards and covers, clear the work area, and complete the site's inspection and lock-removal process. Each lock is removed by its owner or under the site's formal exception process. Notify affected operators and use the approved restart sequence. Observe the restart from a safe location and stop if abnormal sound, vibration, heat, or protection trips recur. Record work and hand back the equipment.

# Escalation

Stop work and contact the responsible supervisor or qualified specialist when the hazard, fault, measurement, or procedure is unclear; when protection trips repeatedly; or when smoke, arcing, unexpected motion, severe vibration, or uncontrolled heat occurs. This synthetic guide supplements but does not replace site rules, risk assessment, training, equipment-specific instructions, or applicable regulations.